Sample Quantity Takeoff

Project: 3966 Iowa Street | Excerpt from a 900+ line-item takeoff (CSI Divisions 02-33) | Prepared by Estimation 360

ITEM #	DWG REF	DESCRIPTION	QUANTITY	UNIT
		SELECTIVE REMOVALS AND DEMOLITIONS		
		DEMOLITION		
		SITE REMOVAL		
1	C1-C2	Remove Alley Pavement	996.21	SF
2		Sawcut	39.99	LF
3		Remove Curb & Gutter	50.01	LF
4		Remove A.C Pavement	12.86	SF
5		Remove Concrete Sidewalk	34.04	SF
6		Remove Concrete Walk	174.06	SF
		ERROSION & SEDIMENT CONTROL		
		CONSTRUCTION ENTRANCE		
7	C300	8" Thk Stabilized Construction Entrance	6.64	CY
8		Filter Fabric	267.73	SF
		CONCRETE WASHOUT		
9		Concrete Washout Plastic Lining (60 Mil Polyet	12.60	SF
		SILT FENCE		
10		Silt Fence 2"x2" Wood Stake Filter Fabric Clot	258.01	LF
		GRAVEL BAG		
11		Gravel Bag	71.07	LF
		CONCRETE		
		STRUCTURAL CONCRETE		
		SLAB ON GRADE		

ITEM #	DWG REF	DESCRIPTION	QUANTITY	UNIT
12	S200	5" Thk Concrete Slab on Grade (2991 SF)	46.53	CY
13		5" Thk Concrete Patio Slab (58 SF)	0.90	CY
14		Thickened Slab (1.6 SF)	0.87	CY
15		15 Mil Vapor Barrier	3,050.00	SF
		CONTI. FOOTING		
16		CF1.5: (1'-6" x 24") Conti Footing	7.11	CY
17		CF2.0: (2'-0" x 24") Conti Footing	57.76	CY
		PAD FOOTING		
18		(3' x 3' x 16") Pad Footing	0.89	CY
19		(4'-6" x 3' x 14") Pad Footing	0.58	CY
		SLAB BASE		
20		4" Clean Sand Bedding	37.28	CY
21		Compacted Subgrade	3,050.00	SF
		REINFORCEMENT		
22		Slab on Grade Reinforcement #4 @18" O.C.E.W	2,665.00	LBS
23		Conti Footing Reinforcement 2-#5 T&B	267.00	LBS
24		Conti Footing Reinforcement 3-#5 T&B	2,340.00	LBS
25		Pad Footing Reinforcement	104.00	LBS
		Formwork		
26		Formwork for Slab on Grade	126.00	SF
		GYPCRETE		
27		3/4" Gypsum Floor Topping	5,291.00	SF
28		1/4" Sound Reduction Mat	5,291.00	SF
		METALS		
		COLUMN		

Sample excerpt only - the full takeoff runs 900+ line items across CSI Divisions 02 through 33 (earthwork, concrete, metals, finishes, MEP, utilities).